

Tuckpointing Scope of Work

Complete as needed:

- Seal movement cracks with flexible caulk
- Install flexible caulk around perimeter of windows, doors and vents
- Install flexible caulk around perimeter of window A/C's to Mapps panel
- Install flexible caulk in sill joints, Mapps panels to pre-cast concrete, pre-cast concrete to brick masonry and pre-cast concrete to pre-cast concrete joints
- Repair expansion joints
- Patch damaged concrete
- Patch steel lintels
- Install metal drip edge